

Index

File No. E-4

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 4 N R. 38 E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None. Corner established with this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located on a ridgetop about 300' East of a draw. There is a fence bearing N19°W, 75' East of corner and a fence bearing E-W about 275' South of corner.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature

Willie R. Well

Title

Land Surveyor

Division

Headquarters

Pendleton, Or.

Date

9-02-88

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position determined by survey...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 22" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram. Compass declination 19° East.

ACCESSORIES: DESCRIBE NEW B^T's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

There are no trees within limits, so I marked 2 bearing objects as follows: A 18"x12"x12" above ground point on a large rock outcrop brs S31°W, 115.1' marked "XBO" on East face. Bearing object is near the Southeast edge of the rock outcrop, which is about 50' E-W dimension & 200' N.S. dimension.

A 6'x6' flat spot on the same rock outcrop, at the East edge of the outcrop, brs S52½°W, 110.1' marked "XBO" on top. This area was marked

Work Done By W.R.Wells Title Land Surveyor Date 9-02-88 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared? Yes X Filed At: County Surveyor Date

REMARKS

because it offers one of the only smooth, flat spots on the outcrop. Painted the "XBO" marks in red paint.

Index File No. E-4 T. 4 N R. 38 E W.M. Tract or Surv. No. Cor.