


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-3

History of original corner establishment:

None. Corner established with this survey.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position determined by survey...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 20" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

New bearing trees established:

A 8" white fir brs S53½°W, 45.4' scribed C1/4S7 BT.
A 18" white fir brs N67½°W, 101.3' scribed C1/4S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 14° East to match true bearings.

I hereby certify that the above described corner monument was properly established by me on August 31, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of Umatilla
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 17th day of October..... 1988
David H. Krumbein..... by Kathleen K. Amshewitz.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-88
Rec'd By KH
No. 88-64-B