

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-5

History of original corner establishment:


Corner established by Robert F. Omeg, U.S. Deputy Surveyor, under his Contract No. 761, dated June 16, 1905.

Surveyor General records state:

Set a basalt stone 18x12x6 ins. 14 ins. in the ground for 1/4 sec.cor. marked 1/4 on W. face; from which,

A fir 6 ins. diam. bears S12°E, 57 lks dist marked 1/4S8 BT.

A fir 6 ins. diam. bears S85°W, 195 lks dist marked 1/4S7 BT.



Description of corner evidence found:

Found an upright 18x12x6" basalt stone with fractured west face on a mound of stone from which:

A 12" douglas fir brs S86°W, 87.1' with scribes visible on opened blaze. (OBT)

A 12" douglas fir brs S22°E, 37.6' with scribes vislble on opened blaze. (OBT)

NOTE: Mound of rocks and corner stone were painted with yellow paint.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position of found stone...

Set 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe 22" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post North of corner with sign 54-4 attached. Cap marked as shown in corner diagram. Buried corner stone in new mound.

New bearing trees established:

A 13" ponderosa pine brs S6°W, 2.0' scribed 1/4S7 BT.

A 6" douglas fir brs N82°E, 32.9' scribed 1/4S8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-4 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly remonumented by me on August 12, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor..... County of... Umatilla.....
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 12th day of... October..... 19 88
David H. Kumbain..... by... Kathleen Kumbain.....
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-88

Rec'd by *KA*

No. 88-64-B