

Index

File No. H-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 4 N 38 E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None. Corner established with this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located on steep East slope about 200' East of ridge, near the North edge of an opening.

Signature
Walter R. Weel

Title Land Surveyor

Division _____
Headquarters Pendleton, Or.

Date 8-31-88

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position determined by survey...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 24" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post North of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

Compass declination 16° East.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 14" ponderosa pine brs N53½°W, 63.1' scribed C-S1/16S7 BT.

A 28" ponderosa pine brs N14°W, 31.9' scribed C-S1/16S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Work Done By W.R.Wells Title Land Surveyor Date 8-31-88 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes XXXX Filed At: County Surveyor

Date

REMARKS

Index File No. H-3 T. 4 N R. 38 E

WM.

Tract or Surv. No.

Cor.