

OREGON CORNER RESTORATION FORM

Section 24,19,25,30 Township 4N Range 37 & 38E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: R-25

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin under contract No.304, dated Sept. 19th, 1879. The corner was a fir, 18 ins. diam. from which: a fir, 12 ins. diam. brs. N.54°E., 26 lks. dist. A fir, 9 ins. diam. brs. S.66°E., 22 lks. dist. A fir, 8 ins. diam. brs. S.27°W., 17 lks. dist. A fir, 5 ins. diam. brs. N.60°W., 46 lks. dist.

It was resurveyed by Robert F. Omeg under contract No. 761, dated June 16th, 1905. It was resurveyed again by Otis F. Gould, under Special Instructions, Group 234, dated 7/11/1939. Gould found a dead and fallen fir tree 14" in diam. with marks grown over. He set an iron post 3 ft. long 2 ins. diam., 27 ins. in the ground, for the Cor.of Secs. 19,24,25 & 30, with brass cap marked as indicated in the monument detail.

A dead fir 14" in diam., brs. S.66°E., 22 lks. dist. marked T4N R38E S30 BT. (old BT)

A fir stump 12" in diam., brs. S.27°W., 17 lks. dist., marked BT (old BT)

A fir stump 14" in diam., brs. N.60°W., 46 lks. dist., marked T4N R37E S24 BT. (old BT)

A fir 6" in diam., brs. N.32 1/2°E., 20 lks. dist., marked T4N R38E S19 BT.

A fir 6" in diam., brs. S64 1/2°E., 12 lks. dist., marked T4N R38E S30 BT.

A fir, 6" in diam., brs. S.38 1/2°W., 20 lks. dist., marked T4N R37E S25 BT.

A fir 6" in diam., brs. N.59 1/2°W., 44 lks. dist., marked T4N R37E S24 BT.

Monument(s) & Accessories Found: (Condition and Source) Found the monument described in the monument detail, from which;


A 10" fir stumped marked 4N R37 brs. N.55 1/6°W., 30.8 feet.

A 14" fir marked 4N R37, brs. N.52°E. 13.9 ft.

A 11" fir stump marked 4N R37E S25 brs. S44 1/2°W. 13.0 ft.

A 10" fir with a Boise Cascade location sign attached brs. N.29°E., 3.1 ft.

Monument Detail:



Monument Set (Procedures and Description):The exiting monument was solidly set and in good condition.

New Accessories:A 12" fir brs. S.32 1/2°E., 28.6 ft., marked T4N R38E S30 BT.

A 11" fir brs. S.57°W., 23.8 ft., marked T4N R37E S25 BT.

A 20" fir brs. N.71°W., 36.8 ft., marked T4N R37E S24 BT.

A steel fence post with a Land Survey Monument sign attached brs. W. 2.9 ft.

Location & Comments: The corner in on a steep bushy N.W. slope approximately 60' S. of the bottom.

Compass Declination: 18° E

Firm/agency: Tomkins-Wells Joint Venture

Land Surveying

P.O. Box 1696

Pendleton, Oregon 97801

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Todd Rosenbalm

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

93-64-C