

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


**History of original corner establishment:**

Corner established by Frank Campbell under G.L.O. contract number 468 dated April 12, 1883.

Surveyor General's records state:

Set a basalt stone 10" x 10" x 8", 7" in the ground for 1/4 sec cor marked 1/4 on the N face. from which:

A tamarack 6" diam bears N 10° E., 17 lks dist. marked 1/4 S BT  
An alder 4" diam bears S 05° W., 50 lks dist. marked 1/4 S BT



R-15

**Description of corner evidence found:**

NONE

**Description of monument and accessories established to perpetuate the original location of this corner**

Set a 2 1/2" brass cap on a 2" iron pipe 31" long in rock mound near top edge of talus slide with a 6 ft. steel fence post 6 ft. north with sign 54-4 attached.

new bearing trees:

A fir 8" diam. bears S 48° E., 35.5 ft. dist. marked 1/4 S 27 BT  
A fir 14" diam. bears N 89° W., 60.5 ft. dist. marked 1/4 S 22 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of Aug., 1976  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)