

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 38E., W.M.

Corner Code No. T-13

Note: Monument marked as shown below

History of original corner establishment:

Corner was originally established by Frank Campbell under Contract No. 468 dated April 12, 1883.

The original notes state:

Set a basalt stone 13 ins. X 10 ins. X 6 ins., 9 ins. in the ground for 1/4 corner marked 1/4 on W face from which:

A fir 18 ins. diam. bears S 80° E, 56 lks dist. marked 1/4 S BT.
A fir 20 ins. diam. bears N 78° W, 98 lks dist. marked 1/4 S BT.

In 1976, J.D. Hanley found the original record sized corner stone in place, marked 1/4 on west face and X on top. Hanley also found the decomposed remains of the original bearing trees at record bearings and distances from the corner.

Certificate Record No. Q-22 states:

Set a 2 1/2" brass cap on 2" iron pipe 31" long 6" above ground in earth and rock mound with a 6" steel fence post with sign 54-4 attached alongside.

Note: I buried the stone on north side of the brass cap monument.
New bearing trees:

A pine 10" dia. bears S 47° E, 6.0 ft dist marked 1/4 S 27 BT.
A fir 9" dia. bears N 77° W, 25.5 ft dist marked 1/4 S 28 BT.

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe projecting 1" out of mound of stone from which:

A 10" dead lodge pole pine bears S 47° E, 6.0' with visible scribes on a partly healed double blaze. (Hanley)
A 10" dying white fir bears N 77° W, 25.5' with visible scribes on a partly healed double blaze. (Hanley)

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained monument by remounding and cleaning up around it.
Set steel fence post South of monument with sign 54-9 attached.

Marked 4 new bearing trees:

A 12" Englemann spruce bears S 78 1/2° E, 29.1' scribed 1/4 S 27 BT.
A 20" Englemann spruce bears N 21° E, 31.6' scribed 1/4 S 27 BT.
A 18" western larch bears N 48 1/2° W, 39.1' scribed 1/4 S 28 BT.
A 21" Englemann spruce bears S 87 1/2° W, 13.9' scribed 1/4 S 28 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 1-92

Rec'd By KK

No. 92-01-R

☆ GPO—798-276