

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 38E. , W.M.

Corner Code No. T-14


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Victor Mc Lind as shown on Record Map No. R-176-C. The Map states:

Set 2" X 30" galv. iron pipe with brass cap from which:

New BT, a fir, 8" diam., scribed "CW 1/16 S27 BT", bears N 89 1/2° E, 42.8 ft.
New BT, a spruce, 8" diam., scribed "CW 1/16 S27 BT", bears N 45 1/2° W, 15.7 ft.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe flush with ground from which:

A 13" white fir bears N 89 1/2° E, 42.8' with healed double blaze. (Mc Lind)
A 10" blown down Englemann spruce bears N 45 1/2° W, 15.7' with scribes visible on double blaze. (Mc Lind)

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained monument by cleaning up around it and mounding with earth.

Set steel fence post South of corner with signs 54-2 and 54-9 attached.

Marked 1 new bearing tree:

A 19" western larch bears S 28 1/2° W, 24.1' scribed C-W 1/16 S27 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 1-92
Rec'd By AK
No. 92-01R

★ GPO—798-276