

USDA-FOREST SERVICE

Index

File No. T-12

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 4N R. 38E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T4N R38E
W 1/16
C _____ C
S27
1980
RLS 934

DESCRIBE CORNER MONUMENT FOUND

Found 2 1/2" brass cap on a 2 1/2" galv. iron pipe, flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 13" white fir bears N 89 1/2° E, 42.8' with healed double blaze. (RLS 934)
A 10" blown down englemann spruce bears N 45 1/2° W, 15.7' with scribes visible on double blaze. (RLS 934)

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located near the west side of a clearcut, about 300' west of a road running in a southwesterly direction.

Signature

Will R. Well

Title

PLS

Division

Headquarters

Pendleton, OR 9/4/91

Date

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Maintained monument by cleaning up around it and mounding with earth.
Set steel fence post south of corner with signs 54-2 and 54-9 attached.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Marked 1 new bearing tree:

A 19" western larch bears S $28\frac{1}{2}^{\circ}$ W, 24.1' scribed C-W 1/16 S27 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze.
Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band
around all bearing trees.

Work Done By W.R. Wells Title PLS Date 9/4/91 State Registration No. 1106
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor Off. Date 12/91

REMARKS

Index File No.

T-14

T.

4N

R.

38E

M. Will

Tract or Surv. No.

Cor.