

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: T-5

One Quarter Corner, Secs. 29 & 30, T4N, R38E, WM.

Corner originally set by Frank Campbell in contract 468 dated 1883. His record reads:	1	DIAGRAM	1
Set a post 3 1/2 feet long 3 ins square with marked stone 24 ins in ground for 1/4 sec cor	1		1
marked 1/4 S on W face from which	1	1/4	1
A fir 13 ins dia bears N53W 7 lks dist marked 1/4S BT	1	S30 S29	1
A fir 12 ins dia bears S33E 33 lks dist marked 1/4S BT	1	1939	1
In 1939, Gould under special instruction	1		1
remonumented the corner. His record reads:	1		1
40.27 proportionate measurement. Set an iron post,	1		1
3 ft. long, 1 in. diam., 27 ins. in the ground, for 1/4 sec. cor. with brass cap marked(see diagram) from which A spruce, 34 ins. diam., bears S.41°E., 5 lks. dist., marked 1/4 S 29 BT. A spruce, 26 ins. diam., bears N.50°W., 12 lks. dist., marked 1/4 S30 BT.			

Description of corner evidence found:

Found 2 1/2" standard GLO brass cap stamped as shown in diagram above. From which a 24" dbh Engleman Spruce bears N50°00'W, 8.0' with healed blaze; a 34" dbh Engleman Spruce bears S41°00'E, 3.3' with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set the following new witness trees:
 A 17" dbh Alpine Fir bears S71°00'W, 43.7', scribed 1/4 S30 BT.
 A 19" dbh White Fir bears N10°49'E, 58.5', scribed 1/4 S29 BT.
 The bearings are based on the bearings to the existing NW BT.
 A brass washer stamped ORLS852 and WALS 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was done August 17, 1995 and witnessed by Stephen Haddock.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

Office of SURVEY County of Umatilla
 State of OREGON, I hereby certify that the within instrument was filed
 in this office for record on the 23rd day of October, 1995.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-95
 Rec'd By KK
 No. 95-179-B