


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX: II-6

History of original corner establishment:

A. Corner not established by GLO



Description of corner evidence found:

B. MONUMENT FOUND:

none

Description of monument and accessories I established to perpetuate the original location of this corner:

C. T set in place a 2.5 inch dia. by 30 inch long aluminum monument 24 inches in the ground. No stones available.

I mark the cap:

T4N R38E WM
SW 1/16
S29 +
1989
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED with magnetic declination of 21 deg. East

10" true fir bears N88E at 17.5 ft scribed "SW 1/16 S29 BT"

12" lodgepole pine bears S00E at 23.8 ft scribed "SW 1/16 S29 BT"

Painted red band around each bearing tree.

Placed brass washer marked "PLS 2060" at base of blaze on each new BT

Placed USDA Forest Service metal signs 54-3 (BT) and 54-4 (ATTENTION) on each bearing tree.

Placed 54-9 (LSM) and 54-2 (PROPERTY BOUNDARY) on steel fence post set 5 feet east of corner.

Office of Survey Dept. County of Umatilla
 State of Ore. I hereby certify that the within instrument was filed in this office
 for record on the 6th day of November, 1989
David A. Humbein by Edwin A. Stryker
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 11-89
 Recd. By RS
 No. 89-107-B

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Edwin A. Stryker
 OREGON
 JULY 15, 1983
 EDWIN A. STRYKER
 2060