


V-12

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



V //

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 2" below road surface with a steel fence post 6' long 2' west with a sign 54-4 and 2 signs 54-2 attached.

from which:

- A spruce 11" diam. bears N 30° W., 24.3 ft. dist. marked E1/16 S 28 BT
- A spruce 14" diam. bears S 44° W., 33.3 ft. dist. marked E1/16 S 33 BT

Each BT has a sign 54-3 attached 5" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of.....Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 26 day of Aug., 1976
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)