


History of original corner establishment:

Corner originally established by Frank W. Campbell under contract # 468 dated April 12, 1883. Set a basalt stone 20"x15" x 4" 15" in ground with 1 notch on S. and 3 notches on E. from which: a 12" spruce bears N 14° E 178 lks a 12" spruce bears S 30° E 65 lks a 10" spruce bears S 74° W 28 lks a 12" spruce bears N 63° W 183 lks



In a U.S. Dependent resurvey by Otis O. Gould in August 1939 found stone and set a 2" x 36" iron pipe with a brass cap 27" in the ground from which: a 8" pine bears N 42 1/2° E 40 lks (26.4 ft) a 8" pine bears S 28 1/2° E 38 lks (25.1 ft) a 12" pine bears S 55 1/2° W 46 lks (30.4 ft) a 9" pine bears N 35 1/2° W 55 lks (36.3 ft)

V-13

Description of corner evidence found:

a 8" down pine root hole bears N 42 1/2° E 26.4 ft. scribe marks visible a 8" down pine root hole bears S 28 1/2° E 25.1 feet scribe marks visible a 15" pine bears S 55 1/2° W 30.4 feet scribe marks visible a 12" down pine root hole bears N 35 1/2° W 36.3 feet lying on face (* Lodgepole pine)

At corner I found 2" iron pipe with brass cap stamped as diagram

Description of monument and accessories I established to perpetuate the original location of this corner:

I drove a steel fence post 3 feet West and attached 54-4 sign. New bearing trees a 9" pine bears N 84° W 12.3 feet scribed T 4 N R38E S 28 BT A 9" fir bears N 24° E 25.8 feet scribed T 4 N R38E S 27 BT a 6" fir bears S 64° E 20.4 feet scribed T 4 N R38E S 34 BT

I nailed alum. tags stamped 951 to bottom of blazes and painted blazes red. Painted red band around BT's and nailed USFS 54-3 and 54-4 signs to them.

(*Lodgepole pine)

I hereby certify the above corner location was perpetuated as herin described in July, 1985.

Jud Coppock, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 18, 1871 G. DENNIS EDWARDS 951

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-6-85

Rec'd By RA

No. 85-102-R

95-c