

T 4N, R 38E., W.M.

Corner Code No. V-13


Note: Monument marked as shown below

History of original corner establishment:

Corner was originally established by Frank Campbell under Contract No. 468 dated April 12, 1885. Original notes state:  
 Set a basalt stone 20 ins. x 15 ins. x 4 ins. 15 ins. in ground with 1 notch on S. and 3 notches on E., from which:  
 A spruce, 12 ins. diam. bears N 14° E 178 lks.  
 A spruce, 12 ins. diam. bears S 30° E 65 lks.  
 A spruce, 12 ins. diam. bears S 74° W 28 lks.  
 A spruce, 12 ins. diam. bears N 63° W 183 lks.

In a G.L.O dependent resurvey by Otis Gould in 1939, the original corner stone was found and re-monumented with a 2" by 36" iron pipe set 27" in the ground with a brass cap. New bearing trees were marked as follows:  
 A pine, 8 ins. diam. bears N 42 1/2° E 40 lks dist. marked T4N R38E S27 BT.  
 A pine, 8 ins. diam. bears S 28 1/2° E 38 lks dist. marked T4N R38E S34 BT.  
 A pine, 12 ins. diam. bears S 55 1/2° W 46 lks dist. marked T4N R38E S33 BT.  
 A pine, 9 ins. diam. bears S 35 1/2° W 55 lks dist. marked T4N R38E S28 BT.

This corner was maintained by Dennis Edwards in 1985, as noted on Certificate Record No. B5-102-R, See Sheet 2 of 2 for a statement of evidence found and established by Edwards.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe 6" out of small mound of stone from which:

- A 8" down lodge pole pine bears N 42 1/2°E, 26.4' with visible scribes. (1939 bearing tree)
- A 8" down lodge pole pine bears S 28 1/2°E, 25.1' with visible scribes. (1939 bearing tree)
- A 15" lodge pole pine bears S 57°W, 30.4', with visible scribes on a partly healed blaze. (1939 bearing tree)
- A 12" down lodge pole pine bears N 35°1/2 W, 36.3' with visible scribes on under side. (1939 bearing tree)
- A 10" lodge pole pine bears N 84°W, 12.3' with visible scribes on a partly healed blaze. (Edwards)
- A 9" down alpine fir bears N 24°E, 25.8' with visible scribes on a partly healed blaze. (Edwards)
- A 7" alpine fir bears S 64°E, 20.4' with visible scribes on a partly healed blaze. (Edwards)

Description of monument and accessories established to perpetuate the original location of this corner:

There is a steel fence post 4' West of corner with 54-2 and 54-4 signs attached.

Maintained monument by mounding with earth and stone.

Marked 1 new bearing tree:

A 15" Englemann spruce bears N 56 1/2°E, 24.1' scribed T4N R38E S27 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Painted face of blaze and a 6" red band around all bearing trees. All bearing trees have 54-3 signs and 54-4 or 54-9 signs attached.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 1-92  
 Rec'd By KK  
 No. 92-01-R


T 4N, R 38E., W.M.

Corner Code No. V-13

Note: Monument marked as shown below

History of original corner establishment:

Continued from Page 1.....  
 Certificate Record No. 85-102-R by Edwards states:  
 At corner 1 found 2" iron pipe with brass cap stamped as in diagram, from which:  
 A 8" down lodgepole pine root hole bears N 42 1/4° E 26.4 ft. scribe marks visible.  
 A 8" down lodgepole pine root hole bears S 28 1/2° E 25.1 ft. scribe marks visible.  
 A 15" lodgepole pine bears S 55 1/2° W 30.4 feet scribe marks visible.  
 A 12" down lodgepole pine root hole bears N 35 1/2° W 36.3 feet lying on face.  
 New bearing trees:  
 A 9" lodgepole pine bears N 64° W 12.3 feet scribed T4N R38E S28 BT.  
 A 9" fir bears N 78° E 25.8 feet scribed T4N R38E S27 BT.  
 A 6" fir bears S 64° E 20.4 feet scribed T4N R38E S34 BT.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by ..... (DEPUTY)  
 (COUNTY OFFICIAL)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 1-92  
 Rec'd By AK  
 No. 92-01-R