


History of original corner establishment:

None



W-13

Description of corner evidence found:

Found 1 1/4" iron bar N. 88° 20' E 5.36 feet from corner

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2"x30" iron pipe 29" in ground with brass cap stamped as diagram, from which:

a 10" spruce bears N 8 1/2° W 19.0 ft. scribed N 1/16 S 33 BT  
a 1 1/4" iron bar bears N 88° 20' E 5.36 feet behind which I drove a steel fence post and attached a 54-3 and a 54-9 sign. Also attached an alum. tag stamped 951 to the iron bar.  
I nailed alum. tag stamped 951 to bottom of blaze and painted blaze red. painted red band around BT and nailed USFS 54-3 and 54-9 signs to it.

Drove a steel fence post 4 ft North and attached a 54-9 sign

I hereby certify the above corner location was perpetuated as herein described in July, 1985

*Jud Coppock*

Jud Coppock, witness

REGISTERED PROFESSIONAL LAND SURVEYOR

*G. Dennis Edwards*

OREGON JULY 18, 1971 G. DENNIS EDWARDS 951

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-6-85

Rec'd By KA

No. 85-105-R