


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 12

T 4 N R 38 E

History of original corner establishment:

No previous history




Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 2" x 30" iron pipe with a 2 1/2" brass cap stamped 20" in the ground and placed stones to the top from which:  
 a 7" pine bears N 82° W 11.0 ft. scribed CE 1/16 S 33 BT Lodgepole Pine  
 A 11" fir bears N 87° E 3.2 feet scribed CE 1/16 S 33 BT



I nailed Alum. tags stamped 951 to bottom of blazes and painted blazes red. painted red band around BT's and nailed USFS 54-3 and 54-9 signs to them.

I drove a steel fence post 3 feet north and attached a 54-9 sign.

I hereby certify the above corner location was perpetuated as herein described in July, 1985.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
 JULY 18, 1971  
 G. DENNIS EDWARDS  
 951

*Jud Coppock* Jud Coppock, Witness

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-6-85

Rec'd By KD

No. 85-100-R

95-C