


T 4 N R 38 E

History of original corner establishment:  
Corner originally established by George S Pershin  
under contract #304 dated Sept 19, 1878  
Set a spruce post from which:  
A 16" spruce bears N 30° W 10 lks  
A 18" pine bears S 38° W 64 lks



2-11

In 1903 John W Kimbrell under contract # 700 found  
the above bearing trees and set a 3" x 36" fir post  
marked 1/4 S 33 on North face 24" in the ground  
from which:

A 4" pine bears S 89° W 5 lks (3.3 ft.)  
A 4" pine bears N 33° E 15 lks (9.9 ft.)

In a U.S. Dependent Resurvey by Otis O Gould in August 1939 old BT's were  
used to set a 1"x36" iron pipe with B.C. marked as diagram 27" in ground.  
from which:

A 8" fir bears N 35° W 17 lks (11.2 Ft.)

Description of corner evidence found:

Found 1" iron pipe with brass cap firmly in ground (marked as Diagram)  
from which:

A 16" pine\*stump bears S 89° W 3.3 ft. part of blaze visible  
A 12" down pine\*root hole bears N33° E 9.9 ft. some scribe marks visible  
A 14" fir bears N 35° W 11.2 ft. some marks visible on partially healed blaze

\* Lodgepole pine

Description of monument and accessories | established to perpetuate the  
original location of this corner:

I drove a steel fence post 3 ft. east and attached a 54-4 sign.  
New bearing tree

A 13" pine\*bears N 12° E 13.5 ft. scribed 1/4 S33 BT

I nailed alum. tag # 951 to bottom of blaze and painted all blazes red.  
Painted red band around all BT's and nailed 54-3 and 54-4 signs to them.

\* Lodgepole pine

I hereby certify the above coner location was  
perpetuated as herein described in July, 1985

*Jud Coppock* Jud Coppock, Witness

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

RECEIVED BY

(DEPUTY)

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-6-85

Rec'd By KA

No. 85-111-R

95-C