


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

2-5

History of original corner establishment:

Corner established by George S. Pershin under GLO Contract No. 304 dated Sept 19, 1978 Iron Post with Brass Cap established by Otis S. Gould, BLM Surveyor in July 1939 during Dependent Resurvey of part of Subdivision of T4N, R38E from which:




- A Pine 14" dia. S 45°W 12 lks mkd R 38E BT (old BT)
A dead Tamarack 16" dia, N 70°W 18 lks mkd T4N, R38E S31 BT (old BT)
A Spruce 20" dia. N 4 1/2°E 18 lks mkd T4N, R38E S 32 BT (New)
A Spruce 18" dia. N 49°W 37 lks mkd T4N, R 38E, S 31 BT (New)

Description of corner evidence found:

Iron Post 2" dia, set 24" in ground with Brass Cap marked:

Found

12" Spruce bears N 22°W 15.50 ft. mkd T4N, R 38E, S 31 BT



Description of monument and accessories established to perpetuate the original location of this corner

Scribed:

- A 13" Douglas Fir N 32°E 36.1 ft mkd T4N, R38E, S 32 BT
A 10" Douglas Fir S 27°E 18.5 ft mkd T3N, R38E, S 6 BT

Blazes are painted red, trees have red bands painted around them and have signs number 54-3, 54-4, and have Brass Washers stamped PLS 933 nailed to them.

November 1982

By: D. Krumbein
Witness: R.D. Panches
B.J. Reynolds



Office of Surveyor Umatilla County of Umatilla
State of Oregon
for record on the 22 day of July 1983
David H. Krumbein by (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 9-13-83
Rec'd by Bc
No. 83-172-R