

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

---

History of original corner establishment:

Index: Z-5

Cor. Secs. 31 and 32, T.4N., R.38E., W.M.  
 Original corner was set by Pershin in June 1879.  
 His notes record:  
 Set Fir post for cor. to Sec. 31, 32, 5 and 6:  
 A Tamarack 8 ins. di. brs. N.42°E. 16 lks. dist  
 A Pine 10 ins. di. brs. S.80°E. 18 lks. dist  
 A Pine 10 ins. di. brs. S.56°W. 12 lks. dist  
 A Tamarack 10 ins. di. brs. N.70°W. 18 lks. dist  
 In 1939, the GLO remonumented this corner.  
 Their record reads:  
 Set an iron post, 3 ft. long, 2 ins. diam., 27 ins.  
 in the ground, with brass cap marked (diagram)  
 from which

1	DIAGRAM	1
1		1
1	T4N R38E	1
1	S31 1 S32	1
1	-----	1
1	T3N R38E	1
1	S6	1
1	1939	1
1		1
1		1

A pine, 14 ins. diam., brs. S.45°W., 12 lks. dist., marked R38E BT. A dead Tamarack, 16 ins. diam., brs. N.70°W., 18 lks. dist., marked T4N R38E S32 BT. A spruce, 20 ins. diam., brs. N.4 1/2°E., 18 lks. dist., marked T4N R38E S32 BT. A spruce, 18 ins. diam., brs. N.49°W., 37 lks. dist., marked T4N R38E S31 BT.

In 1982, PLS 933 added 2 new BT's to this corner. They are described:  
 A 13" Douglas Fir N32°E 36.1 ft mkd T4N, R38E, S32 BT.  
 A 10" Douglas Fir S27°E 18.5 ft mkd T3N, R38E, S6 BT


Description of corner evidence found:

Found the iron pipe as described with brass cap stamped as shown in the diagram. From this monument:  
 A 14" dbh White Fir, dead and down, N26°52'W, 15.5' with visible BT scribe.  
 A 21" dbh Engleman Spruce N35°57"E, 36.6' with partially healed scribed blaze  
 A 15" dbh White Fir S27°30'E, 18.7' with partially healed scribed blaze.


Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between this section corner and the 1/4 corner to the east as recorded by RPE 2808 in a filed Umatilla County survey. I set the following new witness trees:  
 A 20" dbh Engleman Spruce bears N22°30'W, 22.8' scribed T4N R38E S31 BT;  
 A 18" dbh Engleman Spruce bears S18°17'W, 18.0' scribed T4N R38E S5 BT.  
 An aluminum washer stamped RLS 852 is nailed between the letters B and T on each new tree. All four living trees have LSM and BT signs attached. Painted 6" red bands around all four living trees and painted the scribe blazes red.

This work was done July 11, 1992.



*David L. Haddock*



Office of \_\_\_\_\_ County of \_\_\_\_\_  
 State of \_\_\_\_\_, I hereby certify that the within instrument was filed  
 in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.  
 \_\_\_\_\_ by \_\_\_\_\_  
 ( COUNTY OFFICIAL ) ( DEPUTY )

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 8-92  
 Rec'd By KF  
 No. 92-94-R