


2-6

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



2-6

Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2 $\frac{1}{2}$ " brass cap on a 2" iron pipe 31" long in earth and rock mound 6" above ground with a 6' steel fence post 3' east with signs 54-4 and 54-2 attached.

from which:

A fir 12" diam. bears N. 36° W., 57.7 ft. dist. marked W1/16 S 32 BT
A larch 18" diam. bears N 60° E., 38.9 ft. dist., marked W 1/16 S 32 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla
Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Q-1244-R