


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by George S. Pershin under GLO Contract No. 304 dated Sept. 9, 1978

Iron Post with Brass Cap established by Otis S. Gould, BLM Surveyor in July 1939 during Dependent Resurvey of part of subdivision of T4N R38E from which:


A Pine 20 " dia., bears N 50 $\frac{1}{2}$ ⁰E, 15 lks dist. mkd T4N, R38E, S 33 BT (old)
A Tamarack 12" dia., bears N 61 $\frac{1}{2}$ ⁰W, 30 lks dist., mkd T4N, R38E, S 32 BT (old)



Description of corner evidence found:

Found a 2" Iron Post with 2 $\frac{1}{2}$ " Brass Cap set 24" in ground mkd

Down BT 20" stump N 50⁰E 10.4 feet
Standing BT 14" N 60 $\frac{1}{2}$ ⁰W 19.1 feet



Description of monument and accessories established to perpetuate the original location of this corner

Scribed:

A 18" Tamarack N 16⁰E 29.3 ft. mkd T4N, R38E, S 33 BT.
Blaze is painted red, tree has a red band painted around it and has sign numbers 54-3, 54-4, and has a Brass Washer stamped PLS 933 nailed to it.

November 1982

By: D. Krumbein
Witness: R.D. Punches
B.J. Reynolds



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 22 day of July 1983
David H. Krumbein by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 9-13-83
 Rec'd by BC GPO 796-200
 No. 83-173-R