


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin, under General Land Office Contract No. 430. Surveyor General's records state:

Set a post 4' long 4 ins. square in a mound of stone on S.W. slope for cor. to Sec. 10, 11, 14 and 15. Marked T4S S11 on NE and R30E S14 on SE, S15 on SW and S10 on NW, also with 4 notches on S and 2 notches on E edges.



J-17

Description of corner evidence found:

Found old mound of stone with an old E-W fence line approx. 15' South, Since the old mound was obviously not part of the fence, I made a careful search in the center of the mound and found a soft hole with the remains of rotten wood in the hole. Found spring branch 5.8 ch. south of evidence as per original notes.

Since the evidence found is harmonious with corners 1/2 mi. South and 1/2 mi. East, the center of the mound is accepted as the corner position.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown in the diagram, set 16" in the ground and raised a mound of stone around the pipe. From which:

A juniper 8 in. dia. bears S62°E, 116.8 ft. scribed T4S R30E S14 BT.
A pine 14 in. dia. bears S58°W, 146.3 ft. scribed T4S, R30E, S15 BT.
No other trees available.

Set steel post with warning sign 7 ft. North from corner.
Nailed bearing tree signs and brass washers stamped PLS 848 to trees.
Painted a red band around each tree.

I hereby certify that the above corner monument was reestablished on 8/4/81 as herein described.

Witnesses: D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

Office of... Co. SURVEYOR..... County of... Umatilla.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the 7th day of January....., 1982
David L. ... by *City State*
(COUNTY OFFICIAL) (DEPUTY)

82-01-C