


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882, by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state:  
Set a basalt stone 12 x 10 x 8 ins. 8 ins. in the ground on S.W. slope for 1/4 Sec. Cor. Marked 1/4 on N. face. No trees, raised mound of stone alongside in lieu of pits.



J-19

Description of corner evidence found:

Found 13"x11"x9" basalt stone set in ground with 1/4 on North face; a mound of stone East alongside.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 16" in the ground and raised a mound of stone around the pipe.

No bearing trees available. Set a steel post with warning sign 5' North from corner.

I hereby certify that the above corner monument was reestablished on 7/31/81 as herein described.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Witnesses:

\_\_\_\_\_  
D. Mitchell Ferguson

\_\_\_\_\_  
Mike Woodward

Office of...County Surveyor..... County of...Um\_tilla  
State of...Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the...7<sup>th</sup> day of...January....., 1982  
.....*David Krumholz*..... by *Billy Shatto*.....  
(COUNTY OFFICIAL) (DEPUTY)