


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-~~2~~ 2/

History of original corner establishment: Corner originally established by George Pershin in 1882: Set a basalt stone 15"x12"x8", 10" in the ground on a slight south slope marked with 4 notches on south and one notch on east edge from which bears:

- A pine 18" in diameter, N28°E, 205 lks. marked T4S R30E S12 BT.
- A pine 12" in diameter, S83°E, 76 lks. marked T4S R30E S13 BT.
- A pine 13" in diameter, S78°W, 113 lks. marked T4S R30E S14 BT.
- A pine 10" in diameter, N76°W, 56 lks. marked T4S R30E S14 BT.



In 1978 the BLM perpetuated this corner as follows: Set a brass capped iron pipe in the original mound of stones (a marked stone was not found) from which original BTs bear: (Continued on Page 2)

Description of corner evidence found: I found the brass capped BLM Monument in a mound of stones and properly marked. Recent road construction has destroyed the remains of the original S.E. bearing tree as well as the new one set in 1978.

I found the following bearing trees:

- A 45" ponderosa pine bears N28°E, 134.6 ft. (record 205 lks.). The upper blaze has been partly opened, the lower blaze healed over. No marks are visible.
- A 36" ponderosa pine bears S78°W, 38.5 ft. (record 113 lks.). Both blazes are healed.
- A 23" ponderosa pine bears N76°W, 54.1 ft. (record 56 lks.). The upper blaze has been partly opened, the lower blaze healed over.

Description of monument and accessories I established to perpetuate the

original location of this corner: From the brass capped corner monument I blaze and scribe the following tree:

- A 12" ponderosa pine bears S59°E, 105.7 feet scribed "T4S R30E S13 BT" on a single blaze. The centerline of the new road is 30 feet East of the corner, and runs in a N-S direction.

Compass declination: 20°East

I hereby certify the above corner point was perpetuated as hereon described on November 14, 1983.

Witness: Susan E. Newstetter



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 24 day of January, 1983.
 by Betty Cochran.....
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd By BLC
084-6-R