


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under general land office Contract No. 430. Surveyor General's records state:
Set basalt stone 14x12x8 ins. 10 ins. in ground on slight east slope in open glade for 1/4 Sec. Cor. marked with 1/4 on N face. No trees, raised a mound of stone alongside in lieu of pits.



J-7

Description of corner evidence found:

No evidence found, old fence construction has destroyed all traces of corner monument.

Found 2 unrecorded bearing trees which face proportioned corner position; therefore, I accepted proportion position as the 1/4 corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 14 inches in the ground and raised a mound of stone around the pipe.

No bearing trees available.
Set steel posts with warning signs 6 ft. East and 6 ft. West from corner.

I hereby certify that the above monument was reestablished as herein described on 9/10/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

Witnesses
D. Mitchell Ferguson

Mike Woodward

Office of Co. Surveyor County of Umatilla
State of Oregon
for record on the 7th day of January, 1982
Daniel P. Rumbert by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)