

USDA-FOREST SERVICE

Index File No. K-20

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_

Cor. No. \_\_\_\_\_

T 45 R. 30E

R.D. Ukiah

County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



T45 R30E  
NE 1/16 S 14  
1981  
PLS 848

DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is in open pine timber on SW slope;  
approx. 700 ft. West from primitive N-S road.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

*Signature*

Title  
PLS 848

Division

Headquarters

Date

Mt. Vernon, OR

7/31/81

7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 16 inches in the ground and raised a mound of stone and earth around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 9 in. dia. bears N66°E, 35.1 ft. scribed NE 1/16 S 14 BT.  
A pine 20 in. dia. bears N 2°E, 34.0 ft. scribed NE 1/16 S 14 BT.  
Set steel posts with warning and boundary signs 5 ft. West and 5 ft. North from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.  
Painted a red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 7/31/81 State Registration No. OR PLS 848  
or Agency

Certified Correctly Reported? Yes  No  Filed At: Umatilla Co. Surv. Off. Date 10/81

PROFESSIONAL  
LAND SURVEYOR

REMARKS

Witnesses to above corner:  
D. Mitchell Ferguson  
Mike Woodward

OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848