


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



K-25

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 14 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 16 inches dia. bears N19°E, 26.4 ft. scribed N 1/16 S 18 BT.

A pine 10 inches dia. bears S36°W, 44.3 ft. scribed N 1/16 S 13 BT.

Set steel posts with warning and boundary signs 5 ft. West and 5 ft. South from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted a red band around each tree.

I hereby certify that the above corner monument was established as herein described on 8/5/81.

REGISTERED PROFESSIONAL LAND SURVEYOR

*[Signature]*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor ..... County of... Umatilla .....  
State of... Oregon .....  
I hereby certify that the within instrument was filed in this office  
for record on the... 7<sup>th</sup>... day of... January... 1982  
... *David Brown* ... by *Betty Shedd* ...  
(COUNTY OFFICIAL) (DEPUTY)

82-81-C

T-2