

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 13  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on June 15, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 18" x 10" x 6", in a mound of stone, on rocky ground, for 1/4 section corner, marked 1/4 on west face. from which:

A 14" pine bears N67° E, 150 links (99.0 feet).  
No other trees.

**Original corner evidence recovered:**

The original corner stone is gone, apparently in the rock-jack at the fence corner nearby. From the corner point, a sawn 33" Ponderosa Pine stump with a healed blaze bears N67° E, 99.0 feet. I open the healed blaze to scribes, "BT".

**Monument and accessories established to perpetuate the original position of this corner:**

At record bearing and distance from the original bearing tree remains, I set a 1" x 18" flared, galvanized iron pipe 14" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe, from which:

- A 7" Ponderosa Pine, scribed "1/4 S15 BT", bears N35° 30' E, 118.1 feet.
- A 34" Ponderosa Pine, scribed "1/4 S15 BT", bears S77° E, 158.1 feet.
- A 10" Ponderosa Pine, scribed "1/4 S16 BT", bears S87° W, 107.5 feet.
- A 13" Ponderosa Pine, scribed "1/4 S16 BT", bears N85° W, 82.9 feet. I nail a "Bearing Object" sign above the blazes on this tree.
- A fence corner with wire fences projecting north, south and east, bears S12° W, 20.5 feet. I nail a "Witness Post" sign to the fence corner post.
- The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on May 21, 2003.  
Magnetic declination set in compass: 14° E.  
NAD '83 UTM Zone 11 position: 5009586N 336237E (plus or minus two meters).


  
*Dennis L. Gaylord*

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

**RECEIVED BY**

Umatilla County Surveyor:  
 Date 9-03  
 Rec'd By KY  
 No. 03-263-R