

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established in 1882 by George S. Pershin:

Set a basalt stone 14" x 12" x 4", 10" in ground on slight south slope for $\frac{1}{4}$ section corner marked " $\frac{1}{4}$ " on west face. From which:

A pine, 22" diam., bears S.15°E., 22 links distance (14.52 ft.) marked " $\frac{1}{4}$ S BT"

A pine, 36" diam., bears S.12°E., 32 links distance (21.12 ft.) marked " $\frac{1}{4}$ S BT"



Description of corner evidence found:

Original corner stone, set in a mound of stones, is marked " $\frac{1}{4}$ " on the west face. Stone measures 15" x 12" x 4".

From which:

A 26" sawn pine stump with scribing, "BT", visible bears S.15°E., 22.6 ft.

A 39" sawn pine stump with scribing, "S BT", visible bears S.12°W., 29.6 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 2 $\frac{1}{2}$ " x 30" iron pipe with a 3" brass cap attached.


Brass cap is marked:

I bury the corner stone alongside and build a mound of stones around the pipe.

From which:

A 13" Ponderosa Pine bears S.29°E., 30.2 ft. scribed " $\frac{1}{4}$ S.13 BT" on double blazes.

An 11" Douglas Fir bears N. 34°30'W, 21.5 ft. scribed " $\frac{1}{4}$ S.14 BT" on double blazes. De: 22°E.



I hereby certify the above corner location was perpetuated as hereon described on January 19, 1981.

Witness: John T. Hall



Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 19 day of..... January....., 1981.
 .. David H. K... .. by ..
 (COUNTY OFFICIAL) (DEPUTY)

S-6-171