


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George Pershin under General Land Office Contract No. 430. Surveyor General's records state:
Set basalt stone 17x10x8 in mound of stone on slight S.E. slope for 1/4 Sec. Cor.



L-25

Description of corner evidence found:

Found old stone mound alongside a rock crib; stone of record size (17x10x8) in center of mound. No marks visible.

No bearing trees originally established.

Since the old mound is not a part of the fence and is harmonious with adjacent found corners, the center of the mound is accepted as the 1/4 corner position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 16 inches in the ground and raised mound of stone around the pipe.

From which:

A pine 10 inches dia. bears N37°W, 43.5 ft. scribed 1/4 S 13 BT.

A pine 20 inches dia. bears N1°E, 16.3 ft. scribed 1/4 S 18 BT.

Set steel posts with warning and boundary signs 5 ft. North and 5 ft. South from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described on 8/6/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor..... County of... Umatilla.....
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 27th day of... January..... 1982
David Krumbein..... by Betty J. Jette.....
(COUNTY OFFICIAL) (DEPUTY)

82-01-C