


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



M-19

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 12 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 14 in. dia. bears W 30.8 ft. scribed CS 1/16 S 14 BT.

A pine 18 in. dia. bears S52°E, 87.2 ft. scribed C S 1/16 S 14 BT.

Set steel post with warning and boundary signs 5 ft. West and 5 ft. East from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to trees.

Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 8/12/81.



Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of Co. Surveyor..... County of Umatilla

State of Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 7th day of January..... 1982

Douglas M. Ferguson..... by *Betty Slatt*

(COUNTY OFFICIAL) (DEPUTY)

82-1-C
T-2