

USDA-FOREST SERVICE


Index
File No. M-20
T 4S R. 30E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____
R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Corner not/viously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on the South slope of an open ridge approx. 600 ft. South of a road which follows the top of that ridge.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature

Title PLS 848 Division _____ Headquarters Mt. Vernon, OR Date 8/12/81
7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 12 inches in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 12 in. dia. bears N38°E, 20.8 ft. scribed SE 1/16 S 14 BT.
A pine 17 in. dia. bears S 18°E, 22.8 ft. scribed SE 1/16 S 14 BT.
Set steel posts with warning and boundary signs 5 ft. West and 5 ft. South from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 8/12/81 State Registration No. or Agency OR PLS 848

Certified Correct Record Prepared? Yes No Filed At: Umatilla Co. Surv. Off. Date 10/81

PROFESSIONAL
LAND SURVEYOR

REMARKS

Witnesses to above corner:
D. Mitchell Ferguson
Mike Woodward

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848