


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



N-20

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv.iron pipe with 3" brass cap, stamped as shown on the diagram, set 16" in the ground and raised a mound of stone around the pipe.

From which:

A pine 11 in. dia. bears N44°W, 100.5 ft. scribed E 1/16 S 14 BT.

A pine 13 in. dia. bears S45°W, 63.9 ft. scribed E 1/16 S 23 BT.

Set steel posts with warning and boundary signs 5 ft. North and 5 ft. South from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described on 8/12/81.

Witnesses: D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of... Co. Surveyor..... County of... Umatilla
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 22... day of... January..... 1982
..... *Donald Krumbein*..... by *Betty Shatto*.....
(COUNTY OFFICIAL) (DEPUTY)