


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



T-22

Description of corner evidence found:

N/A

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 18 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 8 inches dia. bears S13°E, 23.2 ft. scribed CW 1/16 S 25 BT.
A pine 8 inches dia. bears N54°E, 67.7 ft. scribed CW 1/16 S 25 BT.
Set steel posts with warning and boundary signs 5 ft. South and 5 ft. East from corner.
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 7/30/81.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1968 DOUGLAS M. FERGUSON 848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of Co. Surveyor Umatilla County of Oregon, I hereby certify that the within instrument was filed in this office for record on the 25 day of January 1982 David Kruehlein by Betty Sheltz (COUNTY OFFICIAL) (DEPUTY)

82-01-C

T-2