

USDA-FOREST SERVICE

Index File No. T-24

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 4S R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T4S R30E

E 1/16

C ——— C

525

1981

PLS 848

DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on SW side of open SE ridge top, approx. 200 ft. South from a road coursing W-SW. Road intersects main ridge road approx. 800 ft. NE from point North of corner.

Signature

Title
PLS 848

Division

Headquarters

Date

Mt. Vernon, OR 7/29/81

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 6 inches in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 10 inches dia. bears S61°W, 118.2 ft. scribed CE 1/16 S 25 BT. No other tree available.

Set steel posts with warning and boundary signs 6 ft. North and 8 ft. East from corner.

Nailed bearing tree sign and brass washer stamped PLS 848 to tree. Painted a red band around the tree.

Work Done By D.M. Ferguson Title Surveyor Date 7/29/81 State Registration No. or Agency OR PLS 848

Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Surveyor Off. Date

REGISTERED
PROFESSIONAL
LAND SURVEYOR

REMARKS

Witnesses to above corner:
D. Mitchell Ferguson
Mike Woodward

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848