

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: May 20, 1998

CORNER DESIGNATION: A-23, North Quarter Corner of Section 1, Township 5 South, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by George S. Pershin, under Contract No. 430, dated March 23, 1882. Record states: Set a basalt stone 18 x 12 x 5 in. on level in open glade in mound of stone for 1/4 Sec. Cor., marked 1/4 on N. face. Raised mound of stone alongside in lieu of pits.

**MONUMENT AND ACCESSORIES FOUND:**

Found stone of record size, marked 1/4 on North face and a 2 1/2 foot diameter mound of stone on the South side of corner stone.

**MONUMENT MARKING DETAIL:**

T4S R30E  
1 S36  
4 S1  
T5S R30E  
1998  
PLS 1106

**MONUMENT SET:**

At position of found original stone, set a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe 20" in ground and surrounded with mound of earth and stone. Buried original stone on North side of new mound.

**New Accessories:**

A 14" ponderosa pine bears N 5 1/2° E, 86.9 feet scribed "1/4 S36 BT", on double blaze.

An 18" ponderosa pine bears N 66 1/2° E, 71.1 feet scribed "1/4 S36 BT", on double blaze.

A 6" and 8" double juniper bears S 21 1/2° W, 129.8 feet scribed "1/4 S1 BT", on double blaze.

A 22" ponderosa pine bears N 56 1/2° W, 64.9 feet scribed "1/4 S36 BT", on double blaze.

Set steel fence post East of corner with witness sign attached.

Tagged bearing trees with bearing object signs.

**LOCATION AND COMMENTS:**

COMPASS DECLINATION: 18° East

Witnesses: William R. Wells, PLS 1106  
John Linder, LSIT

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-98*

**RECEIVED BY**

Umatilla County Surveyor

Date 5-98

Rec'd by KK

No. 98-104-B