


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-19

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 373, dated September 17, 1880. The original notes state that at the corner a 14" x 12" x 6" basalt stone was set on steep South slope for 1/4 sec. corner from which:



A 18" dia Pine bears S25°W 7 1/2 dist.

No restoration appears in County Records.

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

After a thorough search of the area this corner was re-established by single proportion measure between the S 1/4 and S W corner of Section 34, T3S, R31E based on record distances from retracement survey by Pershin in September 1880, at which point I set:

A 2 1/2" brass cap on 2 1/2" x 30" l. pipe 16" in the ground with mound of stone from which:

A 13" dia Red Fir bears S79°E 48.4 ft dist marked: 1/4 S2 BT.

A 10" dia Red Fir bears S27°W 9.5 ft dist marked: 1/4 S2 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 4 signs.

New BTs have a lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush.

Set steel fence post with 54-2 & 4 signs West of corner.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 21, 1982.


Cap marked:

Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of.....County Surveyor..... County of.....Umatilla.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the...15... day of...December... 19.82

Daniel H. Drumbeinby .. *Betty L. Shatto* ..
(COUNTY OFFICIAL) (DEPUTY)

A-19

Form R6-7100-57 (9/71)

REC. IV. D EY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-138-B