


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state:
Set basalt stone 14 x 12 x 12 on South slope, in mound of stone for 1/4 Sec. Cor.



9-25

Description of corner evidence found:

Found a basalt stone 14"x12"x12" with 1/4 visible set in a mound of stone. N-S fence line 5 ft. West from stone, old rail fence line running West.

No bearing trees originally established. Accepted the position of 14"x12"x12" stone as 1/4 Sec. Cor. position.


Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap stamped as shown on the diagram, set 16 inches in the ground and raised a mound of stone around the pipe. Set original stone South alongside pipe.

From which:

A pine 14 in. dia. bears S39°E, 120.4 ft. scribed 1/4 S 7 BT. No bearing tree available on West side. Set steel post with warning sign 5 ft. North from corner. Nailed bearing tree sign and brass washer stamped PLS 848 to tree. Painted red band around tree.

I hereby certify that the above corner monument was reestablished as herein described on 8/11/81.



Witnesses:
D. Mitchell Ferguson
Mike Woodward

Office of..... Co. Surveyor..... County of Umatilla.....
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 12 day of January, 1982
David K. Green by Betty Statts
(COUNTY OFFICIAL) (DEPUTY)

82-01-C