

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 29, 1880, under GLO contract No. 373, as follows:

Set a basalt stone, 18" x 12" x 10", and a post, in a mound of stones on an east slope for the corner to sections 17, 18, 19 and 20.

T4S R31E
~~S18~~S17
S19S20
PLS 1636
2001

Corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 19" x 12" x 8" and is plainly marked with four notches on one edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 12" into the ground to bed rock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I partially bury the corner stone, with the marks down, along the west side of the pipe and build a large mound of stones around the pipe to the cap, from which:

- A 5/8" x 24" iron rod, set 23' into the ground with a 3/4" brass washer, marked "PLS 1636 S17", attached at ground level, bears N31° E, 86.4 feet.
- A 12" Juniper, scribed "T4S R31E S20 BT", bears S57° 30' E, 70.6 feet.
- A 5/8" x 24" iron rod, set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S19", attached at ground level, bears S30°W, 90.7 feet.
- A 5/8" x 24" iron rod, set 18" into the ground with a 3/4" brass washer, marked "PLS 1636 S18", attached at ground level, bears N57°W, 89.3 feet.

The bearing tree is scribed on double blazes, has a 3/4" brass washer, marked "PLS 1636", nailed flush with the scribed "B", and has a Bearing Object sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on June 8, 2001. Magnetic declination set in compass: 18° 30'E.



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 2001.

RECEIVED BY
 Umatilla County Surveyor
 Date 6-01
 Rec'd By KR
 No. 01-92-R