

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 7
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 28, 1880, under GLO contract No. 373, as follows:

T4S R31E
1/4 S20
S29
PLS 1636
1998

Set a basalt stone 18" x 12" x 8" on a northeast slope in a mound of stones for the 1/4 section corner.

Corner evidence recovered:

Found the original corner stone solidly set on the northeast edge of a mound of stones. The corner stone is 22" x 12" x 8" and is plainly marked "1/4" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 22" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 19" Ponderosa Pine scribed "1/4 S20 BT" bears N17°30'E, 131.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S55°30'E, 155.8 feet.
- A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S66°30'W, 109.2 feet.
- A 19" Ponderosa Pine scribed "1/4 S20 BT" bears N28°45'W, 149.0 feet. Both bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The bearing tree to the northwest also has a "Witness Point" sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on August 6, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY

Umatilla County Surveyor
Date 9-98
Rec'd By JK
No. 98-182-R