


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 27, 1880, under GLO contract No. 373, as follows:

Set basalt stone 17" x 10" x 10" in a mound of stones on east slope for 1/4 section corner.



Corner evidence recovered:

Found the original corner stone solidly set on the east edge of a mound of stones. The corner stone is 16" x 16" x 12" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 15" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I place the corner stone along the northwest side of the pipe and build a mound of stones around the pipe, and over the corner stone, to the cap, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N30°15'E, 128.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S37°E, 102.7 feet.

The easterly 8" bole of a double bole Ponderosa Pine scribed "1/4 S29 BT" on double blazes bears S64°30'W, 245.2 feet. A 5/8" brass washer, marked "PLS 1636", is nailed flush to the scribed "B". A "Bearing Object" sign is nailed above the blazes and a "Witness Post" sign is nailed to the westerly bole.

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 S29", attached at ground level, bears N48°30'W, 89.9 feet.

I hereby certify the above corner point was perpetuated as hereon described on July 3, 1998. Magnetic declination: 18°E. This corner is approximately 200 feet south of an east-west barbed wire fence.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 8-98
Rec'd By LR
No. 98-159-R