

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 5  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 28, 1880, under GLO contract No. 373 as follows:

T4S R31E  
1/4  
S31|S32  
PLS 1636  
1998

Set a basalt stone 12" x 10" x 8" on a south slope for quarter section corner, from which:

- A 8" pine bears S61°E, 41 links (27.06 feet).
- A 24" pine bears N45°W, 52 links (34.32 feet).

Original corner evidence recovered:

There is a small mound of stones at the corner point, but the original corner stone is gone, from which:

- A 21" sawn Ponderosa Pine stump with the lower portion of a healed over axe face bears S61°E, 27.1 feet.
- A down and decayed 30" Ponderosa Pine has scribes "1/4S BT" visible on double blazes. Root hole bears N45°W, 34.3 feet.

Monument and accessories established to perpetuate the original location of this corner.

At the corner point as determined by reference from the original bearing tree remnants, I set a 1" x 30" iron pipe 22" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe to the cap, from which:

- A 7" Ponderosa Pine scribed "1/4 S32 BT" bears N23°E, 46.5 feet.
- A 13" Ponderosa Pine scribed "1/4 S32 BT" bears S78°E, 25.2 feet.
- A 14" Ponderosa Pine scribed "1/4 S31 BT" bears S55°30'W, 93.4 feet.
- A 19" Ponderosa Pine scribed "1/4 S31 BT" bears N7°15'W, 46.5 feet.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Witness Post" sign nailed to the back of the tree. The four new bearing trees and the original bearing trees remnants have a "Bearing Object" sign nailed above the blazes. This corner is 10' north of a east-west barbed wire fence.

I hereby certify the above corner point was perpetuated as hereon described on July 9, 1998. Magnetic declination: 18°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

RECEIVED BY

Umatilla County Surveyor

Date 8-98

Rec'd By JK

No. 98-162-R