

USDA-FOREST SERVICE

Index File No. A-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. 1/4


T 4S R. 32E

R.D. Ukiah County Umatilla

Merid. W.M.

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None set.

2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

3

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_

*Signature*

6

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 600 feet east of Forest Service road and about 90 feet north of boundary fence.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_

*Agency*

8

*Barry B Barbour*  
 Signature

Title P.L.S. Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 11/8/77 7100-52-(3/68)

4

5

## CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2½"x30" galvanized pipe with brass cap marked:

Set pipe 18" in the ground with mound of stone around.

OR PLS 1051
T3S R31E
T4S R32E
1/4 S6
1977

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which: A tamarac 24" in dia. bears S34°E, 97.5 ft., scribed 1/4 S6 BT. A pine 8" in dia. bears S79°W, 6.4' scribed 1/4 S6 BT. Placed 54-3s and 54-4s on trees, brass washer on BT blazes stamped PLS 1051. Placed 54-2 and 54-4 fence post 6' east of corner. Painted 6" red bands and both blazes red.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/8/77 State Registration No. OR PLS 1051  
 or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

## REMARKS

Witnesses to the above: D.L. Landers, S. Nelson

12

Index File No. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_ M. \_\_\_\_\_ Tract or Surv. No. \_\_\_\_\_ Cor. \_\_\_\_\_

13