

USDA-FOREST SERVICE

Index
File No. E-2

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor. W1/16
No. _____


T 4S R. 32E

R.D. Ukiah County Umatilla

Merid. W.M.

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 150 feet south of a track road and 40 feet east of a north-south fence.

Signature

Barney B Barbour

Title
P.L.S.

Division _____

Headquarters _____

Date

11/16/77

7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 22" in the ground with mound of stone around.

T4S R32E
 S6
W ———+——— 1/16
 S7
 OR PLS 1051
 1977

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which: a pine 12" in dia. bears N58°E, 28.7 feet, scribed W1/16 S6 BT. A pine 11" in dia. bears S01°E, 11.8 feet, scribed W1/16 S7 BT. Placed brass washer on BT blazes, stamped PLS 1051. Placed 54-3s and 54-4s on trees. Placed 54-2, 54-4, and 54-9 on fence post 4' north of corner.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/16/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

Witnesses to the above: D.L. Landers, L. Clemens, S. Nelson

12

Index File No. T. R. M. Tract or Surv. No. Cor.

13