

USDA-FOREST SERVICE


Index
File No. H-3
T 4S R. 32E
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla Tract or Survey No. _____
N.F. Umatilla State Oregon Cor. No. CS1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on a moderate east slope in thick timber. It is about 100 feet east of a south and west bearing fence corner.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature

Boray B Barbour

Title
P.L.S.

Division

Headquarters

Date
11/14/77

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" galvanized pipe with brass cap marked:
 Set pipe 24" in the ground with stone around.

T4S R32E
 S1/16 C S7
 C
 OR PLS 1051
 1977 9

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Fir 12" in dia. bears N81°E, 21.3 feet, scribed S1/16 S7 BT. A Pine 11" in dia. bears N38°W, 11.7 ft., scribed S1/16 S7 BT. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-3s and 54-4s on both BTs. Placed 54-2 and 54-9 on fence post 4' north of corner. Placed 54-2 and 54-9 on fence post 4' east of corner. Painted 6" red band around BTs and painted both blazes red.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/14/77 State Registration No. or Agency OR PLS 1051

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____ 11

REMARKS

Witnesses: D.L. Landers
S. Nelson