


History of original corner establishment:

Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 390, dated May 12, 1881. Surveyor General records state: Set basalt stone 14x12x4 on West slope of ridge for cor. to Sec. 9, 10, 15 & 16. A fir 5 in. di. brs. N14° E, 45 lks. dis. A pine 7 in. di. brs. S45° E, 34 lks. dis. A pine 7 in. di. brs. S7° W, 46 lks. dis. A fir 7 in. di. brs. N45° W, 52 lks. dist.



Corner remonumented by Craig L. Wanless, BLM Cadastral Surveyor under instructions dated July 18, 1977. His record states: The cor. of secs. 9, 10, 15 & 16, monumented with the original unmarked basalt stone 14x12x4 ins., loosely set 1 in. in the ground from which the remains of the original bearing trees: A pine 22 ins. diam., bears S7° W, 46 lks. dist., with scribe marks T4SR visible on partially healed blaze. A fir 21 ins. diam., bears N26° 52 lks. dist., with healed blaze. (record N45° W). At the corner point... Set iron post, 28 ins. long, 2½ ins. diam., 22 ins. in ground with brass cap mkd. (as shown in corner diagram) from which new bearing trees... A fir 13 ins. diam., bears N77° E, 59 lks. dist., mkd. T4SR32ES10 BT. ~~Description of corner evidence found:~~ A fir 20 ins. diam., bears S34° E, 63½ lks. dist., mkd. T4SR32ES15 BT. Deposit corner stone alongside iron post.

Description of corner evidence found:

Found 2½" iron pipe with 3¼" brass cap (as shown in corner diagram) no stone available.

- A 23" ponderosa pine brs S3° W, 31.1' with scribing visible.
- A 20" dead white fir brs S34 ¾° E, 41.5' with scribing visible.
- A 13" dead white fir brs N77¼° E, 38.6' with scribing visible.
- A 24" dead white fir brs N26° W, 34.6' with healed blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set steel fence post next to corner with sign 54-9 & 54-2 attached.

New bearing trees established:

- A 17" ponderosa pine brs N35¼° W, 327.1' scribed T4SR32ES9 BT.
- A 13" western larch brs N41° E, 25.0' scribed T4SR32ES10 BT.
- A 23" ponderosa pine brs S77¼° E, 94.5' scribed T4SR32ES15 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on June 03, 1992.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 7-92

Rec'd By RR

No. 92-80-B