

History of original corner establishment:

1977, Barry B. Barbour, Registered Land Surveyor No. 1051, while surveying section 10 (Umatilla County Survey No. 0-69-A) established the corner as follows:

At surveyed point:


Set 2 1/2" x 30" galvanized pipe with brass cap, 18" in ground and built a mound of stones to the cap.

From which

A Pine 22" in diameter bears N 1° W, 69.5 ft., scribed W 1/16 S 10 BT.

A Pine 8" in diameter bears S 18° W, 48.3 ft., scribed W 1/16 S 15 BT.

Attached a brass washer, stamped PLS 1051, to foot blaze of both BT's.



Description of corner evidence found:

Found 2 1/2" iron pipe, with 2 1/2" brass cap, projecting 10" above the ground, surrounded by a ring of stones, marked as shown, from which:

11" Ponderosa Pine, bears S. 17 1/2° W., 48.3 feet with healed double blaze (Barbour's Record S. 18° W.)

22" Ponderosa Pine stump, bears N. 1° W., 68.1 feet (Barbour's Record 69.5 ft.)

A fence's large rock jack lies 0.5 feet northwest of the monument.



Description of monument and accessories I established to perpetuate the original location of this corner:

New BT:

9" Ponderosa Pine, bears N. 6 1/2° E., 42.6 feet, scribed "W1/16 S10" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze.

DATUM: NAD83(1991)

STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude	Longitude	Northing(y)	Easting(x)
45°13'41.62077" North	118°50'04.04578" West	573723.538	8631159.471

REGISTERED PROFESSIONAL LAND SURVEYOR

*David A. Schlaich*

OREGON  
JULY 16, 1987  
DAVID A. SCHLAICH  
2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....

..... by.....  
(COUNTY OFFICIAL) (DEPUTY)