

History of original corner establishment:

1881, George S. Pershin, U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 390 established the corner as follows:

Set basalt stone 14 X 12 X 5 on steep W. face of bluff for 1/4 Sec. cor.

A Fir 18 in. di. brs. N. 32° E. 19 lks. dis.  
A Pine 15 in. di. brs. S. 2° E. 89 lks. dis.

1977, Barry B. Barbour, Registered Land Surveyor No. 1051, while surveying section 10 (Umatilla County Survey No. 0-69-A) reestablished and described the corner as follows:

Could not find any evidence of the stone called for or any of the bearing trees.


Set 2 1/2" x 30" galvanized pipe with brass cap, 20" in ground with a mound of stones to cap.

New BT's:

20" Pine bears N 46° E, 86.0 ft., marked 1/4 S10 BT

18" Fir bears S 24° W, 80.0 ft., marked 1/4 S15 BT

Placed brass washer, stamped PLS 1051, in foot blaze of both trees.



Description of corner evidence found:

Found a 2 1/2" galvanized iron pipe, with 2 1/2" brass cap, projecting 11" above the ground, marked as shown, from which:

20" Ponderosa Pine bears N. 46° E., 86.0 feet with scribing visible on partially healed double blaze and 1 1/4" brass washer "PLS 1501" nailed to the lower blaze.

18" Fir snag bears S. 24° W., 80.0 feet with scribing visible on partially healed blaze.



Description of monument and accessories established to perpetuate the original location of this corner:

Marked new BT's:

28" Ponderosa Pine, bears S. 45° E., 63.6 feet, scribed "1/4 S15" "BT" on double blaze with 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze.

24" Ponderosa Pine, bears S. 12° W., 66.6 feet, marked with a chopped "X" and scribed "BT" in low blaze with 3/4" brass washer stamped "RLS 2308" nailed to the low blaze.

DATUM: NAD83(1991)

STATE PLANE COORDINATES: Oregon North Zone in International Feet

Latitude	Longitude	Northing(y)	Easting(x)
45°13'41.63814" North	118°49'45.57610" West	573752.585	8632480.904

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David A. Schlaich*

OREGON  
JULY 16, 1987  
DAVID A. SCHLAICH  
2308

RENEWAL DATE: 06/30/2006

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....

..... by..... (COUNTY OFFICIAL) (DEPUTY)

J-15

04-213-B