

USDA-FOREST SERVICE

Index
File No. J-8
T 4S R. 32E
Merid. W.M.


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor. No. E1/16

R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls edge of large clearing on nearly level ground.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Barry B Barbour

Title P.L.S. Division _____ Headquarters _____ Date 11/4/77 7100-52-(3/68)


CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

Set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 18" to bedrock and mound of stone around to cap.

S8
E1/16 
S17
OR PLS 1051
1977

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 9" in dia. bears N58°E, 57.3 ft., scribed E1/16 S8 BT. A pine 17" in dia. bears S80°W, 28.8 ft., scribed E1/16 S17 BT. Placed 54-3s and 54-4s on BTs and brass washer stamped PLS 1051 on BT blazes. Painted blazes red and 6" red band on BTs. Placed 54-2 and 54-4 on fence post 4 feet south. Placed 54-2 and 54-9 on fence post 4 feet north of corner.

Work Done By B.B. Barbour Title P.L.S. Date 11/4/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

Witnesses to the above: D.L. Landers, S. Nelson

Index File No. _____ T. _____ R. _____ M. _____ Tract or Surv. No. _____ Cor. _____