

USDA-FOREST SERVICE


Index
File No. L-7
T 4S R. 32E
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon
Tract or Survey No. _____ Cor. No. C1/4

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on an east slope in thick timber about 20 feet east of a north-south fence.

Barney B. Barlow

Signature _____ Title P.L.S. Division _____ Headquarters _____ Date 11/3/77 7100-52-(3/68)


CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

Set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 24" in ground. Mound of stone around.

C1/4  S17

OR PLS 1051
1977

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Fir 16" in dia. bears S65°E 10.0 ft. scribed C1/4 S17 BT.
A Fir 12" in dia. bears N87°W, 10.5 ft., scribed C1/4 S17 BT.
Placed 54-3 and 54-4 on BTs and brass washers stamped PLS 1051 on BT blazes.
Painted blazes red and red band around BTs, 6".
Placed 54-2, 54-4 and 54-9 on fence post 6' north of corner.

Work Done By B.B. Barbour Title P.L.S. Date 11/3/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

Witnesses: D.L. Landers
S. Nelson